

RECENT PROJECTS

Raymond Terrace and Farley WWTW's Pond Lining Construction

Contract Value: \$2,956,800

Client: Hunter Water Corporation

Client Contact: Tommy Zhang



This project involves modifications to three (3) effluent storage ponds including desludging and dewatering, bulk earthworks, drainage systems, geocomposite linings and HDPE liners. Two (2) of the ponds are located at Raymond Terrace WWTW and one (1) of the third ponds is located at Farley WWTW.



The project included the movement of approximately 15,000m³ of fill with 8,500m³ as imported fill. The ponds were lined with over 60,000m² of geocomposite and 2mm thick HDPE liner.

Each pond is located within an existing WWTW and therefore temporary works were required to isolate the ponds from the remainder of the plant.

The project WAS completed on time in July 2016.

