

# RECENT PROJECTS



## Upgrade Existing SPS TO08, Construct New SPS TO8A and Associated Works at Norah Head

Contract Value: \$1,000,000

Final Value: \$1,000,000

Client: Wyong Shire Council

Client Contact: Martin Drake

Works involved upgrading an existing sewage pump station and construction of a new sewage pump station including the following works:

- Construction of a new sewage pump station including new emergency backup diesel pumpset
- Construction of 15m of DN100 watermain
- Construction of 120m of DN200 uPVC rising main
- Construction of 330m of gravity sewer mains
- Construction of 8 new manholes
- Design, implement, monitor and maintain a suitable temporary sewer bypass system during refurbishment works to existing sewage pump station
- Refurbishment and downsizing of existing sewage pump station
- Construction of 230m of 90PE rising main

The project is currently on track for completion in October, 2015

