

RECENT PROJECTS



Sewer Pump Station FB01 Refurbishment & Sewer Rising Main Replacement

Contract Value: \$3,358,500

Final Value: \$3,979,555

Client: Central Coast Council

Client Contact: Andrew Land

Works involved demolition and reconstruction of existing pipework, valves, supports, and access structures within the wet well, valve pit, flow meter pit, and surge vessel areas.

New aluminium lids, handrails, ladders, and davit points were installed, along with electrical upgrades including new alarm floats, lighting, switchboard, and SCADA integration.

The project also included HDD rising main replacement, air valve restoration, concrete hardstands, and vent pipe upgrades.

Work was completed out under live operational conditions requiring close coordination to maintain system functionality and public safety throughout construction.

The project commenced in November, 2023 and was completed in May, 2025.

